

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT19370/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Sinking of Borewells and Providing Pump and Motor at Kogilu, Kogilu Layout, Agrahara Layout, Thirumenahalli in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				Madhuraj H N		
				In Figures		In Words
1	5	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc (P.NO-47, I.NO-9.4, PRED 12-13 SR)	Each BW	2033.0	10165.00	Rupees Two Thousand Thirty Three Only
2	250	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) (P.NO-47, I.NO-9.1, PRED 12-13 SR) 0 to 50 m	Rmtr	330.0	82500.00	Rupees Three Hundred Thirty Only
3	250	50 to 100 m	Rmtr	432.0	108000.00	Rupees Four Hundred Thirty Two Only
4	250	100 to 150 m	Rmtr	480.0	120000.00	Rupees Four Hundred Eighty Only
5	250	150 to 200 m	Rmtr	507.0	126750.00	Rupees Five Hundred Seven Only
6	250	200 to 250 m	Rmtr	588.0	147000.00	Rupees Five Hundred Eighty Eight Only
7	300	250 to 300 m	Rmtr	630.0	189000.00	Rupees Six Hundred Thirty Only
8	225	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/strips in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes) (P.NO-III, I.NO-84, PRED 12-13 SR)	Rmtr	1389.0	312525.00	Rupees One Thousand Three Hundred Eighty Nine Only
9	25	Providing and fixing 250mm dia PVC pipe and as per specification and directions. (BWSSB SR 13-14, P.No.53 I.no.1 of sl.no.11.)	Rmtr	1188.0	29700.00	Rupees One Thousand One Hundred Eighty Eight Only
10	5	175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR)	Each	104.0	520.00	Rupees One Hundred Four Only
11	45	M.S. Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR)	Each	157.0	7065.00	Rupees One Hundred Fifty Seven Only



 19/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				Madhuraj H N		
				In Figures		In Words
12	5	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15.000 HP 25 stage (P.NO-XXXXIII, I.NO-33, PWD SR 13-14) 15 HP 30 Stage	No	74148.0	370740.00	Rupees Seventy Four Thousand One Hundred Forty Eight Only
13	1375	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc., complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe (SR 13-14 PWD, P.No.XVII Sl.no. 509)	Rmtr	336.0	462000.00	Rupees Three Hundred Thirty Six Only
14	255	Providing & fixing heavy duty collar (P.NO-III, I.NO-86, PRED 12-13 SR)	Rmtr	157.0	40035.00	Rupees One Hundred Fifty Seven Only
15	3000	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia (P.NO-535, I.NO-30 (c), BWSSB 12-13 SR)	Mtr	172.0	516000.00	Rupees One Hundred Seventy Two Only
16	5	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc., completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No.	15525.0	77625.00	Rupees Fifteen Thousand Five Hundred Twenty Five Only
17	110000	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.35	38500.00	and Thirty Five Paise Only
18	5	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No	723.0	3615.00	Rupees Seven Hundred Twenty Three Only
19	15	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 13-14, P.NO.XXIV, Sl.no. 673)	No	1201.0	18015.00	Rupees One Thousand Two Hundred One Only
20	15	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia (PWD SR 13-14, P.NO.XXIV, Sl.no. 659)	No	1678.0	25170.00	Rupees One Thousand Six Hundred Seventy Eight Only

H.V. Y. ————

19/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				Madhuraj H N		
				In Figures		In Words
21	15	Providing and fixing of 50mm GI bend to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	229.0	3435.00	Rupees Two Hundred Twenty Nine Only
22	15	Providing and fixing of 50mm GI Nipple to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	109.0	1635.00	Rupees One Hundred Nine Only
23	15	Providing and fixing of 50mm GI union to the motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	234.0	3510.00	Rupees Two Hundred Thirty Four Only
24	5	Labour Charges for end connection (MR)	No	419.0	2095.00	Rupees Four Hundred Nineteen Only
25	250	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	No	95.0	23750.00	Rupees Ninety Five Only
26	5	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc., Complete for basement out door type. (MR)	No	498.0	2490.00	Rupees Four Hundred Ninety Eight Only
27	5	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No	950.0	4750.00	Rupees Nine Hundred Fifty Only
28	150	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	178.0	26700.00	Rupees One Hundred Seventy Eight Only
29	150	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc., Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr	59.0	8850.00	Rupees Fifty Nine Only
30	15	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)	Mtr	309.0	4635.00	Rupees Three Hundred Nine Only
31	5	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm around the pipe to complete depth the connections from the pipe to the conduit etc., is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia bolts, nuts washers and checknuts etc., the pipe shall have 16 through holes of 122mm dia (P.NO - 552, I.NO - 7 , BWSSB SR 13-14)	No	1782.0	8910.00	Rupees One Thousand Seven Hundred Eighty Two Only
32	5	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No	285.0	1425.00	Rupees Two Hundred Eighty Five Only
33	5	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No	1416.0	7080.00	Rupees One Thousand Four Hundred Sixteen Only
34	15	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc., Complete. 50mm dia (P.NO - 103, I.NO - 13.79.6, PWD SR 13-14)	No	1601.0	24015.00	Rupees One Thousand Six Hundred One Only
35	5	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14)	No	326.0	1630.00	Rupees Three Hundred Twenty Six Only


 13/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				Madhuraj H N		
				In Figures		In Words
36	234	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 5, I.NO - 2.4, PWD SR 13-14)	Cum	296.0	69264.00	Rupees Two Hundred Ninety Six Only
37	520	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm ² including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 102, I.NO - 13.73.1, PWD SR 13-14)	Mtr	384.0	199680.00	Rupees Three Hundred Eighty Four Only
38	234	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 13-14)	Cum	80.0	18720.00	Rupees Eighty Only
					3097499.00	

Signature of the Contractor

Mahesh HN

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19.03.

19/3/16